

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR



S-142
STUD AZI

27S 5W 15

NAD 578178.73 4180893.04
83 43°13'10" 123°16'42"

Station: STUD AZIMUTH

T 27 S, R 5W , Sec 15

Date Set: 1979

Set By (Agency): DCSO

Date Recovered: 8-8-91


Recovered By: SJF

Date Recovered: 11/2000 RWS-SJF

Recovered By: _____

Date Recovered: _____

Recovered By: _____



VERTICAL CONTROL NGVD 29

Elevation: 519.30 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: GPS 3rd ORDER Agency: DCSO CS # 66/39 Proj. # 2008 Date: 1991 2000

HORIZONTAL CONTROL

South Zone O.C.S. 27: Y(Northing) 578,214.07 X(Easting) 1,259,934.66

South Zone O.C.S. 83: Y(Northing) _____ X(Easting) _____

Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1980


Approx. NAD 83 Geographic Position: Latitude 43 13 10.5 Longitude 123 16 37.2

DESCRIPTION and TO REACH

SKETCH

Found: A standard DCSO brass cap stamped
"Stud Azimuth 1979" set in a 6" x 36" bell-
tile protruding 3" above ground.

To reach: Approx. 300 ft. east of intersection
of Sunshine Rd. and N. Umpqua Hwy. Mon. lies
63 ft. north of the centerline of the N. Umpqua
Hwy. and 2 ft. lower than the roadway, 2 ft. south
of a metal witness post set in the northerly R/W
fence, and 38 ft. west of a 5/8" IR at engineers
sta. 177+50.65 on the north side of the Hwy.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.