



OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR



NAD 553818.97 4484357.64  
83 43°10'28" 122° 8'17"

Station: VIRGINIA T 27 S, R 6 E , Sec 32  
Set By (Agency): DCSO  
Date Set: 1974  
Recovered By FLI (DCSO)  
Date Recovered 6-28-84  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_



VERTICAL CONTROL NGVD 29

Elevation: 5187.214 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
Precision: 2nd Agency: DCSO Proj. # 2004-8 CS57/23 Date: 1974

HORIZONTAL CONTROL OCS 27


South Zone State Plane Coordinates: Y(Northing) 553,856.93 X(Easting) 1,563,396.12  
Precision: 1/50,000 Agency: DCSO Proj. # 2004-8 CS57/23 Date: 1975  
Approximate Geographic Position: Latitude 43°10'29" Longitude 122°08'13"

DESCRIPTION and TO REACH

Near boat ramp just south  
of Diamond Lake Lodge.

Stem of brass cap in 2 ft.  
diameter boulder under a bush,  
40 ft. south of boat ramp, 5 ft.  
east of water.

SKETCH



|                  |                 |                                                                |
|------------------|-----------------|----------------------------------------------------------------|
| Reference Marks: | VIRGINIA R.M. 1 | Center of vent pipe west of concrete gas intake (El. 5193.905) |
|                  |                 | 553,983.04 1,563,454.85                                        |
|                  | VIRGINIA R.M. 2 | Brass cap in 2 ft. diameter boulder (El. 5184.790)             |
|                  |                 | 553,942.38 1,563,350.58                                        |

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.