

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: NW DLC #39 0390/0 T 27 S, R 6 W , Sec 1

Set By (Agency): DCSO

Date Set: 1960

Recovered By RWS, SJF


Date Recovered 7/31/86

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



270-06W-01-003 27S 06W 01
NW DLC39

NAD 590132.05 4161367.33
83 43°15' 1" 123°21'11"

VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL **OCS 27**

South Zone State Plane Coordinates: Y(Northing) 590,167.20 X(Easting) 1,240,409.00

Precision: 1/20,000 Agency: DCSO Proj. # 2005-2 Date: 1983

Approximate Geographic Position: Latitude 43°15'02" Longitude 123°21'06"


DESCRIPTION and TO REACH

SKETCH

Monument is a 3/4 in. diam. iron rod set in a 10 in. diam. iron collar, 3 in. below street surface.

TO REACH:

From the intersection of State Highway 99 and Hooker Road (Co.Rd.#171) in T27S,R6W,Sec.1, proceed northerly along Hooker Road approximately 400 ft. to monument in center of road.



A DCSO disk stamped "ARMORY 1983" bears S 0°24'20" W, 241.63 ft. (grid).

Reference Marks:

An "X B01" chisled in the concrete collar of sewer manhole. bears N 16°47'47" E, 69.30 ft. (grid).

A 2 3/8 in. diam. DCSO brass cap stamped "B.O. 2 1986" on a 1/3/8 in. O.D. iron pipe protrudes 2 in. above ground. bears S 82°22'47" E, 21.82 ft. (grid).

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.