

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: SS T 28 S, R 5 1/2 E, Sec 20

Set By (Agency): USFS

Date Set: 1984

Recovered By FLI (DCSO)


Date Recovered 7-19-84

Recovered By Harry Heislein (USFS)

Date Recovered Fall 1985

Recovered By _____

Date Recovered _____



s-124 28S 5 1/2E 20
SS

NAD 540120.86 4482485.26
83 43° 8'13" 122° 8'39"

VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL **OCS 27**

South Zone State Plane Coordinates: Y(Northing) 540,158.95 X(Easting) 1,561,523.87

Precision: 1/50,000 Agency: DCSO/USFS Proj. # 2008-1 CS62/23 Date: 1984

Approximate Geographic Position: Latitude 43°08'13" Longitude 122°08'34"

DESCRIPTION and TO REACH


SKETCH

On concrete boat dock at
South Shore Picnic Grounds.

1/4 inch brass rod set in
concrete dock, 2.1 feet from
west, north, and east edges.

Shown on USGS Quads: Diamond Lake 15'

Diamond Lake
7 1/2'



Reference Marks:	FRITZ	Brass cap in 6" belltile (El. 5186.800)
		540,164.18 1,561,662.73
	FRITZ R.M. 1	Brass cap in 6" belltile (El. 5190.138)
		540,038.34 1,561,602.08
	FRITZ R.M. 2	Brass cap in 6" belltile (El. 5185.890)
		540,118.63 1,561,479.74

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.