



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: RUNWAY
Set By (Agency): Don Garrett
Date Set: 1972 L.S. #0544
Recovered By SJF
Date Recovered May 18, 1984
Recovered By _____
Date Recovered _____
Recovered By _____
Date Recovered _____

T 28 S, R 6 W, Sec 27



NAD 537941.89 4149461.72
83 43° 6' 22" 123° 23' 27"



VERTICAL CONTROL **NGVD 29**

Elevation: 1272.8 ft. NGS Line # _____ USGS Line # _____ OSHD Line # _____
Precision: V/A Agency: Don Bentz Proj. # _____ Date: 1972

HORIZONTAL CONTROL **OCS 27**

South Zone State Plane Coordinates: Y(Northing) 537,977.09 X(Easting) 1,228,503.41
Precision: 1/25,000 Agency: DCSO Proj. # 2005 C.S. 56/9 Date: 1972
Approximate Geographic Position: Latitude 43° 06' 23" Longitude 123° 23' 23"


DESCRIPTION and TO REACH

A 3 inch DCSO disk on a 2 inch iron pipe stamped " RUNWAY 1972 " and protruding 6 inches above the ground.

TO REACH:

From the intersection of Dole Rd. (Co. Rd. #14) and Roberts Mountain Road (Co. Rd. #123) in T29S, R6W, Sec. 1, proceed approximately 2.6 miles to unpaved private road on right. (Locked gate: to obtain key, contact Roseburg Lumber.) Proceed southwesterly along unpaved private road approximately 0.65 miles to monument on right. Monument lies west of a NE/SW fenceline near top of a northwest slope.

SKETCH



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.