



OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: SE COR. S 8 T 29 S, R 6 W, Sec 8  
 Set By (Agency): BLM 300500  
 Date Set: 1958  
 Recovered By RWS, SJF  
 Date Recovered 11/14/85  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_



290-06W-08-005 29S 06W 08  
SE CORNER  
 NAD 519928.10 4140078.77  
83 43° 3'21" 123°25'25"

VERTICAL CONTROL

Elevation: \_\_\_\_\_ NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
 Precision: \_\_\_\_\_ Agency: \_\_\_\_\_ Proj. # \_\_\_\_\_ Date: \_\_\_\_\_

HORIZONTAL CONTROL **OCS27**

South Zone State Plane Coordinates: Y(Northing) 519,963.26 X(Easting) 1,219,120.56  
 Precision: 1/25,000 Agency: DCS Proj. # 2013 Date: 1985  
 Approximate Geographic Position: Latitude 43°03'22" Longitude 123°25'21"

DESCRIPTION and TO REACH

SKETCH


DESCRIPTION:

A BLM disk on an I.P. stamped "T29S R6W S8 S9 S17 S16 1958" firmly set and protruding 9 in. above ground (this monument leans approx. 5 in. northwest of plumb, coordinates are to center of leaning disk).

TO REACH:

Corner is on ridge between west Willis Crk. Rd. (Co. Rd. #88A) and Rice Crk. Rd. (Co. Rd. #43).

NOTE: See DCSO Corner Renewal Records.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.