

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: Z 499. T 30 S, R 4W, Sec 22

Set By (Agency): USC&GS

Date Set: 1949

Recovered By JP-RWS


Date Recovered 3-17-82

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



z-008 30S 4W 22
Z 499
NAD 478925.78 4209200.46
83 42°56'59" 123° 9'37"

VERTICAL CONTROL

Elevation: 804.851 NGS Line # 130 USGS Line # _____ OSHD Line # _____
Precision: 2nd Agency: USC&GS Proj. # 2010-2 Date: 1957

HORIZONTAL CONTROL


South Zone State Plane Coordinates: Y(Northing) 478,961.72 X(Easting) 1,288,242.11
Precision: 1/25,000 Agency: DCSO Proj. # 2010-2 Date: 1975
Approximate Geographic Position: Latitude 42°57'00" Longitude 123°09'33"

DESCRIPTION and TO REACH

Found: A standard USC&GS disk stamped "Z-499 1949" set in a 5' x 5' boulder protruding 2' above the ground.

To reach: From the intersection of State Hwy 227 and Co. Rd. #34 (Days Creek Rd.) in T30S R4W sec. 10, proceed Easterly along State Hwy. 227 2.1 miles to monument on the left.

SKETCH



Reference Marks:

A DCSO disk stamped "Z 499 RM1 1985"
bears N 35°50'07" W, 56.57 ft. (grid) ELEV. 809.256 ft.

A DCSO disk stamped "Z 499 RM1 1985"
bears S 64°11'55" W, 98.38 ft. (grid) ELEV. 808.406 ft.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.