

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: PTS-25 T 30 S, R 5W, Sec 19

Set By (Agency): DCSO

Date Set: 1978

Recovered By JP - RWS


Date Recovered 1-28-82

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



p-078
PTS-25 30S 5W 19

NAD 479754.08 4164103.32
83 42°56'53" 123°19'43"

VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL *OCS 27*

South Zone State Plane Coordinates: Y(Northing) 479,789.81 X(Easting) 1,243,144.75

Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1978


Approximate Geographic Position: Latitude 42°56'53" Longitude 123°19'39"

DESCRIPTION and TO REACH

SKETCH

Found: A standard DCSO disk marked "PTS-25 1978",
Station is set in 6" concrete tile 4" above ground.

To reach: From Gazely Rd. exit #102 go easterly
along southerly side of I-5 on Lawson Bar Rd.
0.1 miles to PTS-25 on the right. Witness post
in fenceline 8' South of station.



Reference Marks:

- A DCSO disk stamped "PTS-25 RM1 1978" bears N 21° 32' 39" E 54.57' (grid)
- A DCSO disk stamped "PTS-25 RM2 1978" bears S 71° 03' 36" E 70.31' (grid)

Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.