

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: WIT. COR. E 1/16 T 31 S, R 4 W , Sec 28

Set By (Agency): BLM

Date Set: 1972

Recovered By JP,RS


Date Recovered 9/14/83

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



910-440-28-008 31S 04W 28
40 E 11.5

144 142007.58 200371.08
22 8200125 185-10 80'

VERTICAL CONTROL

Elevation: 1,771.221 NGS Line # _____ USGS Line # _____ OSHD Line # _____
Precision: 2nd Agency: DCSO Proj. # 2006 Date: 1973

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 442,238.91 X(Easting) 1,282,912.27
Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1973
Approximate Geographic Position: Latitude 42°50'55" Longitude 123°10'28"

DESCRIPTION and TO REACH

SKETCH


DESCRIPTION:

A standard corner brass cap stamped "W.C. E1/16 C---C S28 1972", protruding 6 in. above ground.

TO REACH:

From the intersection of McGinnis Creek Rd. (BLM Rd. #31-4-27) and Upper Cow Creek (Co. Rd. #36) in T31S,R4W,Sec.27, proceed westerly along Co. Rd. #36 0.60 miles to monument on left.

NOTE: Monument will be under water when dam is built.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.