

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: PTS-18  
 Set By (Agency): DCSO  
 Date Set: 1975  
 Recovered By RS, JP  
 Date Recovered 9/14/83  
 Recovered By RWS, SJF  
 Date Recovered 10/24/85  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_


T 31 S, R 5 W, Sec 2



p-071  
PTS-18

31S 5W 2

NAD 460746.28 4184873.24  
 83 42°53'52" 123°14'56"



VERTICAL CONTROL

Elevation: \_\_\_\_\_ NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
 Precision: \_\_\_\_\_ Agency: \_\_\_\_\_ Proj. # \_\_\_\_\_ Date: \_\_\_\_\_

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 460,782.27 X(Easting) 1,263,914.56  
 Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1978  
 Approximate Geographic Position: Latitude 42°53'42" Longitude 123°14'51"

DESCRIPTION and TO REACH

SKETCH

DESCRIPTION:


A brass stem in overpass decking.

TO REACH:

Go to Ritchie Rd. (Canyon Creek, exit 95)  
 overpass crossing of I-5, in T31S, R5W, Sec. 2.

NOTE: DCSO disk stamped "PTS-18 1975"  
 was destroyed. Monument probably graded  
 off by snow plow. Found stem of disk  
 still in overpass decking.

\* Existing coordinates are good to  
 center of stem.



Reference Marks: (Proj. 2013)

A DCSO disk stamped "PTS-18 RM 1 1985"  
 bears N 36°51'00" E, 52.72 ft. (grid) elev. 952.43 ft. third order.

A DCSO disk stamped "PTS-18 RM2 1985"  
 bears N 53°58'10" W, 29.69 ft. (grid) elev. 953.16 ft. third order.

An OSHD disk stamped "R 615 1968"  
 bears N 36°42'21" E, 91.90 ft. (grid) elev. 951.79 ft. third order.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205  
 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas  
 County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.