


2/12/80

OFFICE OF THE

c-063 315 5W 3
CANYON MTN RESET

DOUGLAS COUNTY SURVEYOR

NAD 462901.92 4175357.97
83 42°54'10" 123°17' 4"



T 31 S, R 5W, Sec. 3

Station: CANYON MTN. 1975 RESET 1978

Set By (Agency): DCSO

Date: 1978

VERTICAL CONTROL

Elevation: _____ NGS(USC&GS) Line # _____ USGS Line # _____

Order
Of Precision _____ Agency: _____ Proj. #: _____ Date: _____


HORIZONTAL CONTROL

DCS 27
Oregon State Plane Coordinates: Y(Northing) 462,937.83 X(Easting) 1,254,399.34
(South Zone)

Order
Of Precision 1/25,000 Agency: DCSO Proj. #: 2008 Date: 1978

Approximate Geographic Position: Latitude= 42 54' 11" Longitude= 123 17' 00"

DESCRIPTION: From intersection of Riddle-Canyonville Rd. No. 21 and Ash Creek Rd. No. 299, proceed Southerly along Ash Cr. Rd. 2.75 mi. to a fork. Go left 1.7 mi. to a fork. Go right 0.65 mi. to a fork. Go right 0.60 mi. to a fork. Go left along the ridge top 1.1 mi. to a fork. Go left 0.30 mi. to the end of road. Monument is on hillside approx. 50 ft. right of road approx. 100 ft. before end of road. Station mark is a standard DCSO brass cap marked "CANYON MTN. 1975 RESET 1978" set in a 6"x38" conc. filled bell tile. Monument is 14 inches above ground. Mounded stone around base 3 ft. diam. Monument is on Northerly edge of Dimtrack Rd. approx. 800 ft. Northeasterly from Canyon Beacon. Set witness sign and post 2 ft. W SW of monuments.



VICINITY: Canyonville, approx. 2 1/2 mi. South of;
on Canyon Mtn.

NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.