

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR



p-065
PTS-12

T32S 5W E

NAD	430315.35	4110802.52
BB	42°48'50"	123°15'32"

Station: PTS-12 T 32 S, R 5W , Sec 2

Set By (Agency): DCSO

Date Set: 1975

Recovered By RWS-JP


Date Recovered 1-27-82

Recovered By RWS,SJF

Date Recovered 9/12/85

Recovered By _____

Date Recovered _____



VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 430,354.54 X(Easting) 1,259,903.87

Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1975


Approximate Geographic Position: Latitude 42°48'51" Longitude 123°15'32"

DESCRIPTION and TO REACH

SKETCH

Found: A standard DCSO disk set in 6" diam. concrete filled tile. Disk is stamped "PTS-12 1975". Station is set flush with the ground.

To reach: From the intersection Co. Rd. #36 (Cow Creek Rd.) and I-5 Hwy. (freeway exit no. 88 at Azalea) in T32S, R5W, sec. 2, proceed northerly along I-5, 1.2 miles to monument on the left.



Reference Marks: (Proj. #2013)

A DCSO disk stamped "PTS-12 RM 1 1985"
bears S.28°59'07"E., 38.16 ft. (Grid).

A DCSO disk stamped "PTS-12 RM 2 1985"
bears S.47°55'01"W., 71.64 ft. (Grid).

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.