

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: PTS-3 T 32 S, R 5 W, Sec 30

Set By (Agency): DCSO

Date Set: 1971

Recovered By RS,JP


Date Recovered 8/16/83

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



p-056  
PTS-3

32S 5W 30

NAD 413871.87 4160781.37  
83 42°46' 1" 123°19'58"

VERTICAL CONTROL

Elevation: 1518.002 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: 2nd Agency: DCSO Proj. # 2006 Date: 1973

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 413,908.01 X(Easting) 1,239,822.73

Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1973

Approximate Geographic Position: Latitude 42°46'02" Longitude 123°19'54"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "PTS-3 1971" set flush in NW corner of overpass curbing

TO REACH:

Go to Co.Rd.#97 (Barton Rd.) over-crossing of I-5 (exit 83) in T32S, R5W,Sec.30.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.