

1/30/01


OFFICE OF THE

t-024
TEE PEE

22S 5W 8

DOUGLAS COUNTY SURVEYOR

NAD	741346.62	4176796.22
83	43°39'59"	123°18'51"

T 22 S, R 5W, Sec. 8Station: Tee PeeSet By (Agency): DCSODate: 1978, (FD OK 1991), FD OK 8/00 DCSOVERTICAL CONTROLElevation: 305.04 NGS(USC&GS) Line # _____ USGS Line # _____Order
Of Precision 3rd Agency: DCSO Proj. #: _____ Date: 8/2000HORIZONTAL CONTROLOregon State Plane Coordinates: Y(Northing) 741,381.47 X(Easting) 1,255,835.61
(South Zone)Order
Of Precision 1/25,000 Agency: DCSO Proj. #: 2008 Date: 1979Approximate Geographic Position: Latitude= 43° 40' 00" Longitude= 123° 18' 47"DESCRIPTION: B.C. in belltile 2" below surfaceCap is 25" E. of Hwy. 99 centerline and 25'S. of a driveway centerline. RM 1 and RM 2are B.C. in belltile. Witness posts set 3'from monument and RM's. Cap is stamped"Tee Pee 1978".A DCSO disk stamped "TEEPEE RM 1 1979" bears
N 68° 24' 04" W 50.42' (grid)A DCSO disk stamped "TEEPEE RM 2 1979" bears
S 22° 31' 34" W 118.92' (grid)VICINITY: Drain area along Hwy. 99. Approx.0.40 mi. NE'stly along Hwy. 99 from intersection
of Hwy. 99 and Hwy. 38.NOTE: For Possible Further Information On This Station, Please Contact The Douglas
County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR.
97470 Phone 672-3311 Ext. 272. Douglas County residents outside the
Roseburg calling area dial toll free 1-800-452-0991.

SKETCH

