


OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

s-029 23S 5W 22  
S-451  
NAD 698821.39 4182872.06  
83 43°33' 2" 123°17' 9"



S-029

T 23 S, R 5W, Sec. 22

Station: S-451

Set By (Agency): OSHD

Date: \_\_\_\_\_

NGVD 29

VERTICAL CONTROL

Elevation: 433.10 ~~433.100~~ NGS(USC&GS) Line # \_\_\_\_\_ OSHD ~~USGS~~ Line # 369

Order Of Precision 3rd Agency: DCSO Proj. #: 2010-6 Date: 1956 ADJ.  
CS 60/23

HORIZONTAL CONTROL

OCS 27


Oregon State Plane Coordinates: Y(Northing) 698,855.85 X(Easting) 1,261,912.07  
(South Zone)

Order Of Precision 1/25,000 Agency: DCSO Proj. #: 2010-6 Date: 1978  
CS 60/23

Approximate Geographic Position: Latitude= 43°33'02" Longitude= 123°17'05"

DESCRIPTION: An OSHD bench mark brass cap  
mkd. "S-451", Set on the top of the curb at  
the NE'stly Cor. of a freeway undercrossing  
structure, Approx. 20 ft. higher than the  
freeway.

SKETCH:



VICINITY: Approx. 0.8mi N. along I-5 from  
Rice Hill exit #148.

NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272.. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.