


OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

u-016 24S 7W 29
U-15 RESET
NAD 663530.03 4109093.40
83 43°26'48" 123°33'33"



T 24 S, R 7W, Sec. 29
Station: U-15 1972 Reset 1976
Set By (Agency): DCSO
Date: 1976

VERTICAL CONTROL

NGVD 29
Elevation: 373.236 NGS(USC&GS) Line # _____ USGS Line # _____
Order
Of Precision 2nd Agency: DCSO Proj. #: 2006 Date: 1976

HORIZONTAL CONTROL


NAD 27
Oregon State Plane Coordinates: Y(Northing) 663,564.55 X(Easting) 1,188,134.36
(South Zone)

Order
Of Precision 1/25,000 Agency: DCSO Proj. #: 2006 Date: 1976

Approximate Geographic Position: Latitude= _____ Longitude= _____

DESCRIPTION: A standard DCSO bronze disk
marked "U-15 1972 reset 1976" set in a
concrete filled bell tile 2 ft. N. of the
S'thly R/W fence, 27 ft. S. of the center of
Co. Rd. #33, and 22 ft. E'stly of power pole
"3A 183" and 1½ ft. NE of a witness post.

SKETCH



VICINITY: To reach from the Umpqua P.O.
proceed generally N'thly along Co. Rd. #33
13.7 mi. to station on the right.

NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.