



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: SON T 25 S, R 4 W, Sec 3
Set By (Agency): SCS
Date Set: 1975
Recovered By RWS, SJF
Date Recovered 3/6/87
Recovered By _____
Date Recovered _____
Recovered By _____
Date Recovered _____



WAD 650019.33 4217602.29
62 43°25'11" 123°08'52"



VERTICAL CONTROL

Elevation: 813.776 NGS Line # _____ USGS Line # _____ OSHD Line # _____
Precision: 2nd Agency: DCSO Proj. # 6011-1CS57/25 Date: 1975

HORIZONTAL CONTROL


South Zone State Plane Coordinates: Y(Northing) 650,054.65 X(Easting) 1,296,641.98
Precision: 1/25,000 Agency: DCSO Proj. # 6011-1 CS57/25 Date: 1975
Approximate Geographic Position: Latitude 43°25'12" Longitude 123°08'52"

DESCRIPTION and TO REACH

An SCS 2 1/2 in. dia. disk stamped "SON SCS"
set in an 8 in. dia. concrete filled belltile
protruding 15 in. above ground.

TO REACH;

From the intersection of Thomas Rd.
(Co. Rd. #268) and Nonpariel Rd. (Co. Rd. #19)
in T25S,R4W,Sec.10. proceed northeasterly along
Nonpariel Rd. approximately 1.1 miles to
monument RP 265+49.88 on right.(see DCSO
monument station sheet) Monument SON bears
approx. N 36° E. 585 ft. Monument is near
small grove of oak trees on first hill
north of road.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.