

Douglas County Geodetic Data Sheet


T 25 R 05 WS 04

Station: Q 266

Designation: Q-006

Date Set: 1925 Set By (Agency): USGS

Last Date Recovered: 07/00/1993



VERTICAL CONTROL

NGVD 29 Elevation: 454.520 Feet

Precision: 1ST ORDER Agency: USC&GS

CS File:

Date: 1957

NAVD 88 Elevation: 139.612 Meters

Precision: 1ST ORDER Agency: USGS

CS File:

Date: 1988

HORIZONTAL CONTROL

OCS 27 Y(Northing): 653,424.51 X(Easting): 1,256,034.22 Lat 43° 25' 31" Long: 123° 18' 04"

Precision: Agency: CS File: Date:

OCS 83 Y(Northing): 653,390.00 X(Easting): 4,176,993.55 Lat 43° 25' 31" Long: 123° 18' 08"

Precision: Agency: CS File: Date:

OCS 83/91 Y(Northing): X(Easting): Lat Long:

Precision: Agency: CS File: Date:

OCS 83/98 Y(Northing): X(Easting): Lat Long:

Precision: Agency: CS File: Date:


Scaled Lat 43° 25' 31" Long: 123° 18' 04"

Description:

FD. 3-3/4" DIA. DISK STAMPED "Q 266 454 453.86 1925" SET FLUSH IN CONCRETE CURB OF STATE HWY. 99 BRIDGE OVER CALAPOOYA CREEK. AND SPRR

Comments:

GO TO HWY 99 BRIDGE OVER CALAPOOYA AND SPRR APPROX. 0.3 MILES NORTH OF OAKLAND IN T25S R5W SEC. 4.



Notes:

27 & 83 coord values corrected 12/19/2000.
Corrected 100 ft north to agree with computation sheet.

Note: For further information contact the Douglas County Surveyors Office, Room 105A Douglas County Courthouse, Roseburg, OR 97470. Phone 440-4272 or Fax (541)957-8150. Douglas County Residents outside Roseburg calling area, dial toll free 1-800-224-1619.