



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR



NAD 599949.95 4231169.90
83 43°17' 1" 123° 5'32"

Station: POND
Set By (Agency): DCSO
Date Set: 1972
Recovered By GO, JP
Date Recovered 6/83
Recovered By RWS SJR 11/1999
Date Recovered _____
Recovered By _____
Date Recovered _____

T 26 S, R 3 W, Sec 30



VERTICAL CONTROL NGVD 29

Elevation: 723.58 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 3rd Agency: DCSO Proj. # 2007 Date: 1999

HORIZONTAL CONTROL DCS 27

South Zone State Plane Coordinates: Y(Northing) 599,985.60 X(Easting) 1,310,209.94

Precision: 1/25,000 Agency: DCSO Proj. # 2004-1, C.S. 56/21 Date: 1973

Approximate Geographic Position: Latitude 43°17'01" Longitude 123°05'28"

DESCRIPTION and TO REACH

SKETCH

DESCRIPTION:

A DCSO disk stamped "POND 1972"
set in concrete tile.

TO REACH:

Go to the intersection of Little River Rd.
and Buckhorn Rd.


MONUMENTS HAVE
WITNESS POST AND
SIGNS ALONGSIDE.

NOTE - BOTH RM'S IN POOR CONDITION -
LOOSE LEANING (RWS 11/99)

Reference Marks:

A DCSO disk stamped "POND RML 1983"
bears N 27°30'03" W, 115.32 ft. (grid)

A DCSO disk stamped "POND RM2 1983"
bears N 54°51'57" E, 63.41 ft. (grid)



Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.