


OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: Jane
Date Set: 1974
Set By (Agency): DCSO
Date Recovered: 8-19-91
Recovered By: SJF
Date Recovered: _____
Recovered By: _____
Date Recovered: _____
Recovered By: _____

T 26 S, R 6W, Sec 18



J-017
JANE
26S 6W 18

NAD 612539.39 4136031.97
83 49°18'34" 129°27' 3"

VERTICAL CONTROL NGVD 29

Elevation: 427.836 NGS Line # _____ USGS Line # _____ OSHD Line # _____
Precision: 2nd Agency: DCSO Proj. # 2007 Date: 1991

HORIZONTAL CONTROL


South Zone O.C.S. 27: Y(Northing) 612,574.31 X(Easting) 1,215,073.28
South Zone O.C.S. 83: Y(Northing) _____ X(Easting) _____
Precision: 1/25,000 Agency: DCSO Proj. # 2006 River Floodplain Date: 1974
Approx. NAD 83 Geographic Position: Latitude _____ Longitude _____

DESCRIPTION and TO REACH

Found: A standard DCSO cap stamped "Jane 1974" set flush in top of 8" O.D. 42" concrete filled belltile. Mon. protrudes approx. 6" above ground and is approx. 2 ft. higher than road surface near the westerly R/W fenceline

To reach: From the intersection of Upper Cleveland Rapids Rd. (Co. Rd. #208A) and Garden Vly. Rd. (Co. Rd. #6) in T26S, R6W, sec. 20. proceed northerly along Garden Valley Rd. 1.05 mi. to mon. on lt. at approx. milepost 9.6 and about 300 ft. southerly from intersection with Turkey Crk. Ln.

Reference Marks:



Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.