



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: KOW 1979 T 27 S, R 5 W, Sec 20
Set By (Agency): DCSO
Date Set: 1979
Recovered By JP, RS
Date Recovered 8/10/83
~~FD OK PER 1995-0110 DE GROOT~~
Recovered By DCSO 7/98
Date Recovered _____
Recovered By _____
Date Recovered _____



NAD 576163.51 4169639.34
83 43°12'46" 123°19'12"

NGVD 29

VERTICAL CONTROL

Elevation: 489.13 NGS Line # _____ USGS Line # _____ OSHD Line # _____
Precision: 3rd Agency: DCSO Proj. # 2007 Date: 7/98

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 576,198.76 X(Easting) 1,248,681.03
Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1980
Approximate Geographic Position: Latitude 43°12'47" Longitude 123°19'08"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "KOW 1979" set flush in concrete sidewalk.

TO REACH:

From the intersection of Diamond Lake Blvd. and NE Cummins St. proceed westerly along Diamond Lake Blvd. 196 ft. to monument on left.



Reference Marks:

A DCSO disk stamped "KOW RM1 1979" bears N 62°39'49" E, 148.72 ft. (grid)

ELEV. 491.16 3rd

A DCSO disk stamped "KOW RM2 1979" bears N 78°45'22" W, 491.95 ft. (grid)

ELEV. 481.11 3rd

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.