


OFFICE OF THE

R-044
RIVERSIDE

295 5W 27

DOUGLAS COUNTY SURVEYOR

NAD 506386.61 4179026.71
83 43° 1' 21" 123° 16' 35"



T 29 S, R 5W, Sec. 27

Station: Riverside

Set By (Agency): DCSO

Date: 1978

VERTICAL CONTROL

Elevation: 622.6 NGS(USC&GS) Line # _____ USGS Line # _____

Order
Of Precision GPS Agency: DCSO Proj. #: 2017-1 CS64/22 Date: 1991

HORIZONTAL CONTROL

Oregon State Plane Coordinates: Y(Northing) 506,422.21 X(Easting) 1,258,068.25
(South Zone)

(C.S. 61/1)


Order
Of Precision 1/25,000 Agency: DCSO Proj. #: 2004-16 Date: 1979

Approximate Geographic Position: Latitude= 43°01'21" Longitude= 123°16'30"

DESCRIPTION: A standard DCSO brass cap,

marked "Riverside 1978" set on top of the
W'stly curb along Rose Drive, 20 ft. W. of
the centerline of Rose Drive, 32.5 ft. S. of
the centerline of lower S. Myrtle County Rd.
#18A, and 0.4 ft. higher than the road
surface.

SKETCH



TO REACH: From the intersection of Main St.
and Riverside Dr. (Rd #18A) in Myrtle Creek,
proceed Easterly on Riverside Dr. 0.6 miles
to Rose Dr. and the station on the right.

A DCSO disk stamped "RIVERSIDE RM 1 1978" bears
S 87° 29' 11" E 39.45' (grid)
A DCSO disk stamped "RIVERSIDE RM 2 1978" bears
S 3° 43' 01" W 241.09' (grid)

NOTE: For Possible Further Information On This Station, Please Contact The Douglas
County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR.
97470 Phone 672-3311 Ext. 272. Douglas County residents outside the
Roseburg calling area dial toll free 1-800-452-0991.