


OFFICE OF THE
DOUGLAS COUNTY SURVEYOR




PT-055
PTS-2

228 2W 35

NAD 42 1974.54 42°45'08.14"
82 42°45'08.14" 123°20'36.14"

Station: PTS-2
Set By (Agency): DCSO
Date Set: 1973
Recovered By RWS
Date Recovered 10/15/85
Recovered By _____
Date Recovered _____
Recovered By _____
Date Recovered _____

T 32 S, R 5 W, Sec 30



VERTICAL CONTROL

Elevation: 1467.821 NGS Line # _____ USGS Line # _____ OSHD Line # _____
Precision: 2nd Agency: DCSO Proj. # 2006 Date: 1973

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 412,010.66 X(Easting) 1,236,644.76
Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1973
Approximate Geographic Position: Latitude 42°45'42" Longitude 123°20'36"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "PTS-2 1973" set in a 6 in. dia. concrete filled belltile flush with ground.

TO REACH:

From the intersection of Glendale access Rd. (exit 80) and I-5 in T32S,R6W,Sec.35, proceed northerly along I-5 approx. 1.95 miles to monument on right.



Reference Marks: (Proj. #2013)

A DCSO disk stamped "PTS-2 RM 1 1985"
bears S 53°37'08" W, 42.66 ft. (grid) elev. 1467.339 ft.

A DCSO disk stamped "PTS-2 RM 2 1985"
bears N 39°20'20" W, 39.66 ft. (grid) elev. 1468.105 ft.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.