


Douglas County Geodetic Data Sheet

T 29 R 06 S 01



Station: 570 B

Designation: %-144

Date Set: 1903 Set By (Agency): USC&GS

Last Date Recovered: 08/00/1993

VERTICAL CONTROL

NGVD 29 Elevation: 571.226 Feet

Precision: 1ST ORDER Agency: USGS

Project:

Date: 1988

NAVD 88 Elevation: 175.16 Meters

Precision: 1ST ORDER Agency: USGS

Project:

Date: 1988

NGS Line # L25042 USGS Line #

OSHD Line #

File #

HORIZONTAL CONTROL

OCS 27 Y(Northing): X(Easting): Lat Long:

Precision: Agency: Project: Date:

OCS 83 Y(Northing): X(Easting): Lat Long:

Precision: Agency: Project: Date:

OCS 83/91 Y(Northing): X(Easting): Lat Long:

Precision: Agency: Project: Date:


OCS 27 Scaled Latitude: 43°04'28" OCS 27 Scaled Longitude: 123°21'48"

DESCRIPTION:

A 3.75 INCH DIAMETER USC AND GS DISK STAMPED; 570 B 1903; ON A 3.5 INCH DIAMETER IRON PIPE PROTRUDING 14 INCHES ABOVE GROUND

COMMENTS:

FROM THE INTERSECTION OF DOLE RD; CO RD 14 AND ROBERTS MTN RD; CO RD 123 AND A PRIVATE GRAVEL ROAD IN T29S R6W SEC 2 - NEAR DOLE RD BRIDGE OVER S UMPQUA RIVER - PROCEED SOUTHERLY ALONG PRIVATE ROAD 0.4 MILES TO MONUMENT ON LEFT ON EAST SIDE OF SPRR TRACKS AT SPRR MILE POINT 556.7



Note: For further information contact the Douglas County Surveyors Office, Room 105A Douglas County Courthouse, Roseburg, OR 97470. Phone 440-4272 or Fax (541)957-8150. Douglas County Residents outside Roseburg calling area, dial toll free 1-800-224-1619.