

COUNTY SURVEYOR'S RECORD, DOUGLAS COUNTY, OREGON

RUBENSON & CO. PORTLAND, ORE. 87545


<p><i>Survey No.</i> <i>Made on</i> June 26-28 1930</p> <p><i>In Town.</i> 29 S <i>Range</i> 3 W <i>Sec.</i> 20</p> <p><i>Made for</i> A. V. Ady and the Chieftan Mines Inc.</p> <p><i>Purpose of</i> To make a deed description for the Chieftan Mine and a water right for both parties.</p>	<p><i>Survey No.</i> <i>Made on</i></p> <p><i>In Town.</i> <i>Range</i> <i>Sec.</i></p> <p><i>Made for</i></p> <p><i>Purpose of</i></p>
<p><i>C.S. M8-1</i></p>	

This survey was made to determine a deed description for the Chieftan Mine and was started from a point 200 ft east and 200 ft. North from a creek and fence as called for in a contract between the parties involved.

A point was chosen which fulfilled these conditions using an average course of the creek. All bearings are turned from a Solar observation. A line was ran North to the North Line of section 20 of T 29 S R 3 W and a tie made to the $\frac{1}{4}$ section corner common to sections 17 and 20. The line between the above described $\frac{1}{4}$ section corner and the NW corner of Section 20 was established and found to bear N 89°17'W 2666.7 ft.

The W 1/16 section corner between sections 17 and 20 was then established as being the NW corner of the Property of A.V. Ady. It was then found that using our temporary beginning point a strip some 68 ft wide was left between the description called for in the contract and Ady's west line. This condition was unsatisfactory and it was agreed by the interested parties that the east line of the mining property be 1500 ft east of the west line of the property of A. V. Ady. This was done giving a Deed Description which conveys a parcel of land 1253.3 ft north and south by 1500 ft east and west .

The attached map illustrates the results of this survey and forms a part of this record.


 Ben. B. Irving,
 Deputy County Surveyor.