

COUNTY SURVEYOR'S RECORD, DOUGLAS COUNTY, OREGON

BUSHONG & CO. PORTLAND, ORE. 87545

| | |
|---|---|
| <p>Survey No. 7 Made on Oct. 1933.</p> <p>In Town. 28 S. Range 6 W. Sec 9 - 10</p> <p>Made for The Hiers of L. F. Landers.</p> <p>Purpose of dividing the Estate of L. F. Landers into three parts to the three hiers; Namely Henry R. Landers, Alice V. (Landers) Ormsby, and Gertrude C. (Landers) Hess.</p> <p>Chainman N. E. Richardson.</p> | <p>Survey No. Made on</p> <p>In Town. Range Sec.</p> <p>Made for</p> <p>Purpose of</p> <p style="text-align: center;">SEE M 6-23</p> |
|---|---|


In the division of the Estate of L. F. Landers into three parts to the three hiers, Namely Henry R. Landers, Alice V. (Landers) Ormsby, and Gertrude C. (Landers) Hess, I used the Survey of F. J. Cole and J. " Cole for the exterior boundary of the estate, which are the true boundaries.

I started my survey at a stone, marking the North-East Corner of the property and I ran South 23.6 chains, where I set a 1" x 3' iron pipe for the South-East Corner of Henry R. Landers part and the North-East Corner of Gertrude C. (Landers) Hess part. Thence I ran West 36.59 chains to a point, where I set a 1" x 5' iron pipe, from which an 8" Black Oak, marked C.S.B.T. bears N. 34° E. 31 links. This point is the South-West Corner of Henry R. Landers part and the North-West Corner of Gertrude C. (Landers) Hess Part.

I then return to the North-East Corner of Gertrude C. (Landers) Hess part and continue South 17.36 chains to a point, where I set a 1" x 3' iron pipe for the South-East Corner of Gertrude C. (Landers) Hess part and the North-East Corner of Alice V. (Landers) Ormsby part. Thence I ran N. 87° - 28' W. 54.2 chains to a point where I place a 1" x 5' iron pipe, from which a 12" Cedar, marked C.S.B.T., bears N. 17° W. 34 links; and said point being the South-West Corner of Gertrude C. (Landers) Hess part and the North-West Corner of the Alice V. (Landers) Ormsby, part.

Thence I return to the North-East Corner of The Alice V. (Landers) Ormsby part and ran South 14.7 chains to the South-East Corner of the L. F. Landers Estate, in Township 28 South, Range 6 West, Sections 9 & 10.

Tracing in Drawer 58. Competation and Description in V. 18 E. 37.
Field Note; Loose Leaf.


 County Surveyor.