COUNTY SURVEYOR'S RECORD, DOUGLAS COUNTY, OREGON

BUSHONG & CO. PORTLAND, ORE. 87545

Survey No. **35** *Made on* Aug 6,1936

In Town. 26 S *Range* 5 W. *Sec.* 6

Made for F.W.Baker

Purpose of Division of Property at Serv. Sta. formerly owned by Bill Godsey (N.of Station and for deed descriptions.

A.Boyer Inst &Notes Baker Jr. Chain.



F.W.Baker Survey.

This survey was made from data gathered by and from permanent property corners established by B.B.Irving in a survey made in June, 1926 for Wm.Godsey who owned this property at that time. The points established by Irving were found and checked out as being correctly established; after this was done and the property was run around,a division was made of the property which lays N.&W. of the 10 ft alley as dedicated, this alley is in the N. portion of the property owned by Godsey; and as it was mutually agreed by both Mr F.W.Baker and J.F.Toops in the presence of witnesses, so the division was made and points were set on this dividing line as shown on the annexed map or sketch. the corners of both properties were staked except where traffic would interfere inasmuchas the west part of this property seems to be located within the boundaries of the Pacific Highway.

A.Boyer
Dep County Surveyor.

Survey No. **36** *Made on* Julym15th 1936

In Town. 28 S; *Range* 8 W. *Sec.* 31

Made for Harmsen and Wakefield

Purpose of to establish boundaries of SE¼SW¼

A.Boyer Inst & Rear Chain
Doren Reidenhauer and Willis Grant,help

C. S. File No. 23/47



Harmsen and Wakefield

This survey was started from the South quarter corner of section 31, T.28 S; R,8 W. which is six feet east of an iron bar driven at a fence corner; Harmsen and Wakefield who bought this property from Mr Whiting requested a needle line survey only inasmuch as the value of the property would not justify subdividing the entire section, so a needle line was run around this forty and the corners of the property were set at 1320 ft, distances except as shown at the N.W. corner where Mr Whiting deeded a 200 x 400 ft tract to his motherinlaw for a home. It should be noted that this is not an accurate survey and was not intended to show any close lines but only approximate ones since it will not be fenced by the present owners who bought it primarily for a mill site.

A.Boyer.
Deputy Co Surveyor.