



QUANTITY SUMMARY				
ITEM	UNIT	QUANTITY	ALLOWANCE	TOTAL
1	CLEARING & GRUBBING	L-SUM	ALL	ALL
2	DITCH EXCAVATION	CU YD	1297	133
3	GENERAL EXCAVATION (UNCLASSIFIED)	CU YD	93,080	9310
4	OVERHAUL	C-YD STA	4,021	409
5	FINISHING ROADBED & SLOPES	L-SUM	ALL	ALL
6	TRENCH EXCAVATION (UNCLASSIFIED)	CU YD	1190	120
7	WATERING	M-GAL	2909	291
8	COARSE AGGREGATE BASE	TON	90,191	9019
9	3/4" O AGGREGATE BASE	TON	14,422	1,448
10	3/4" O AGGREGATE IN PRIME COAT	CU YD	1,588	162
11	RC 250 IN PRIME COAT	TON	163	17
12	RSI IN TACK COAT	TON	16	2
13	CLASS "B" ASPHALTIC CONCRETE	TON	24,236	2464
14	18" CONCRETE CULVERT PIPE	LIN. FT.	192	20
15	24" CONCRETE CULVERT PIPE	LIN. FT.	172	16
16	36" CONCRETE CULVERT PIPE	LIN. FT.	156	12
17	12" CULVERT PIPE	LIN. FT.	918	92
18	18" CULVERT PIPE	LIN. FT.	1162	118
19	24" CULVERT PIPE	LIN. FT.	180	20
20	72" x 44" H.E. C.M.P.	LIN. FT.	106	10
21	EXTRA FOR PIPE UNDER PAVEMENT	LIN. FT.	286	34
22	6" PERE DRAIN PIPE	LIN. FT.	270	30
23	SPECIAL BACKFILL IN DRAINS	CU YD	30	3
24	EXTRA FOR AC APPROACHES	EACH	47	3
25	GUIDE POSTS TYPE W-1	EACH	102	10
26	GUIDE POSTS TYPE Y-1	EACH	58	6
27	GUARD RAIL	LIN. FT.	3775	375
28	TYPE 2 BARRICADE	LIN. FT.	200	20
29	LOOSE RIP RAP CLASS 100	CU YD	74	6
30	MAIL BOX STAND (SINGLE)	EACH	13	1
31	MAIL BOX STAND (MULTIPLE)	EACH	12	1
32	ROLLER HOURS	HOUR	557	53

NOT REVISED  
AS CONSTRUCTED

DOUGLAS COUNTY ROAD DEPT  
NORTH UMPQUA HWY RD # 4  
1972 SHT 2  
GEORGE E. GRUBB COUNTY ENGR.

0000QUAN