



TYPICAL SECTION FOR ROAD #4
STA 697+40 ~ 805+99.47

QUANTITY SUMMARY				
ITEM	UNIT	QUANTITY	ALLOWANCE	TOTAL
1	CLEARING & GRUBBING	L-SUM	ALL	ALL
2	DITCH EXCAVATION	CU YD	1146	114
3	GENERAL EXCAVATION (UNCLASSIFIED)	CU YD	49008	4902
4	OVERHAUL	C-YD STA	4,227	423
5	FINISHING ROADBED & SLOPES	L-SUM	ALL	ALL
6	TRENCH EXCAVATION (UNCLASSIFIED)	CU YD	886	84
7	WATERING	M-GAL	2300	230
8	OBLITERATE OLD ROADBED	SQ. YD.	610	60
9	COARSE AGGREGATE BASE	TON	73,237	7323
10	3/4"-O AGGREGATE BASE	TON	11,420	1140
11	3/4"-O AGGREGATE IN PRIME COAT	CU. YD.	1250	130
12	RC 250 IN PRIME COAT	TON	120	12
13	R.S.I. IN TACK COAT	TON	13	2
14	CLASS "B" ASPHALTIC CONCRETE	TON	18,510	1850
15	18" CONC. CULVERT PIPE	LIN. FT.	96	8
16	24" CONC. CULVERT PIPE	LIN. FT.	48	4
17	30" CONC. CULVERT PIPE	LIN. FT.	28	4
18	12" CULVERT PIPE	LIN. FT.	918	92
19	18" CULVERT PIPE	LIN. FT.	66	6
20	24" CULVERT PIPE	LIN. FT.	146	14
21	36" CULVERT PIPE	LIN. FT.	164	16
22	72" CMP (COATED)	LIN. FT.	92	8
23	43"x 27" H.E.C.M.P.	LIN. FT.	50	4
24	EXTRA FOR PIPE UNDER PAVEMENT	LIN. FT.	144	16
25	6" PERF DRAIN PIPE	LIN. FT.	200	20
26	SPECIAL BACKFILL IN DRAINS	CU. YD.	27	3
27	EXTRA FOR A.C. APPROACHES	EACH	26	4
28	GUIDE POSTS TYPE W-1	EACH	81	9
29	GUIDE POSTS TYPE Y-1	EACH	36	4
30	GUARD RAIL	LIN. FT.	3100	300
31	TYPE 2 BARRICADE	LIN. FT.	200	20
32	MAIL BOX STAND (SINGLE)	EACH	3	0
33	ROLLER HOURS	HOUR	270	30

NOT REVISED
AS CONSTRUCTED

DOUGLAS COUNTY ROAD DEPT
NORTH UMPQUA HWY RD #4
1973 SHT 2
GEORGE E. GRUBB COUNTY ENGR.

1337QUAN

RJ #4

1973 05 27 11

66