

SUMMARY

CASCADE LAKES HWY.
 GRADING M.L. 3.681
 " WYE 0.148
 TOTAL 3.829 MILES

STATE	PROJECT NO.	SHEET NO.	TOTAL SHEETS
ORE.	46-A2-B	2	12

COUNTY SURVEYORS FILE
 DO NOT REMOVE FROM OFFICE

GRADING								
STATION	CUBIC YARDS				SPEC. O'HAUL		CU. YDS. OLD ROAD OBLIT.	REMARKS
	EXC.	CH. CH.	BORROW	EMB.	STA. YD.	C.Y.M.		
251+44 4				3300	263		5500	
267+25	4670			4307				
288+85	5857			7103	4137			
308+70	11274			1983				
320+60	3182			2627				
335+00	3908			1975				
342+75	2924			2294	261			
355+07	3361			3264	247			
366+15	4713			3357				
384+35	5218			1864	10			
394+68	2566			4263	5953	10		
415+30	6281			19172	69000	420		
445+80	26198	512						
TOTALS	80152	512	2000	55509	79871	430	5500	

DRAINAGE STRUCTURES				
STATION	LINEAL FEET			REMARKS
	C.M.P.	BIT.COR	STD. CONCRETE	
	18"	24"	36"	
261+10	88			
273+30	42			
278+00	40			Salvage CMP
281+25		80		
294+78			60	
302+00	40			
309+10			62	
314+70	46			
318+20	40			
325+00	42			
330+90	42			
334+00	42			
340+80	42			
345+50	42			
355+12			50	
358+30		50		
361+55	52			
363+68	46			
374+05		44		
377+40	38			Salvage CMP
383+80	44			
387+50	44			
402+60	46			
412+30	40			
423+30	54			
426+07		68		
Totals	78			Salvage Pipe
Totals	792			New "
Totals	870	242	172	Pipe to be Installed