

QUANTITY SUMMARY

ITEM	UNIT	QUANTITY	ALLOWANCE	TOTAL
1. CLEARING & GRUBBING	Lump Sum	ALL	—	ALL
2. GENERAL EXCAVATION (UNCLASS.)	CU YD.	48,503	4,847	53,350
3. FURNISH & PLACE SELECTED FILL (DEVELOPMENT CLASS 7)	CU YD.	7,587	763	8,350
4. OVERHAUL	"C" V. Sta.	2,958.2	291.8	3,250.0
5. FINISHING ROADBED & SLOPES	Lump Sum	ALL	—	ALL
6. DITCH EXCAVATION (UNCLASS.)	CU YD.	663	67	730
7. TRENCH EXCAVATION (UNCLASS.)	CU YD.	648	62	710
8. WATERING	MI-GAL.	718	82	800
9. OBLITERATION OF OLD ROADBED	STA.	30	5	35
10. COARSE CRUSHED MATERIAL IN BASE	TON	28,380	2,320	31,200
11. 3/4"-0 MATERIAL IN BASE	TON	9,000	900	9,900
12. 3/4"-0 MATERIAL IN PRIME	CU YD.	447	53	500
13. RS-1 ASPHALT IN PRIME	TON	102	13	115
14. ASPHALT CONCRETE PAVEMENT	TON	5,664	586	6,250
15. 12" CULV. PIPE	Lin. Ft.	652	68	720
16. 18" CULV. PIPE	Lin. Ft.	364	36	400
17. 24" CULV. PIPE	Lin. Ft.	96	9	105
18. 36" CULV. PIPE	Lin. Ft.	148	17	165
19. 60" C.M.P.	Lin. Ft.	186	19	205
20. MAIL BOX STAND (SINGLE)	EACH	17	3	20
21. MAIL BOX STAND (MULTIPLE)	EACH	2	1	3
22. ROLLER HOURS	HOURS	200	20	220
23. GUARD RAIL	Lin. Ft.	2,625	275	2,900
24. RAIL END PIECES	EACH	18	2	20
25. GUARD RAIL BLOCKS	EACH	245	25	270
26. EXTRA FOR A.C. APPROACHES	EACH	25	4	30

DOUGLAS COUNTY ROAD DEPT.
 ROSEBURG RESTON LOOP #5
 DATE: SEPT 69 SHEET 2 OF 10
 GEORGE E. GRUBB COUNTY ENG.

0342QUAN

PJ # 5