QUANTITY SUMMARY

	ITEM	UNIT	QUANTITY	ALLOWANCE	TOTAL	
1.	CLEARING and GRUBBING	Lump Sum	ALL	—	ALL	
2.	GENERAL EXC. (Unclassified)	Cu. Yd.	14,120	1,430	15,550	
3.	OVERHAUL	C"Yd.Sta.	—	—	—	
4.	FINISHING ROADBED and SLOPES	Lump Sum	ALL	—	ALL	
5.	TRENCH EXC. (Unclassified)	Cu. Yd.	140	15	155	
6.	DITCH EXC. (Unclassified)	Cu. Yd.	176	24	200	
7.	WATERING	M-Gal.	373	37	410	
8.	COARSE CRUSHED MATERIAL IN BASE	Ton	15,118	1,532	16,650	
9.	3/4"-0 MATERIAL IN BASE	Ton	5,047	503	5,550	
10	3/4"-0 MATERIAL IN PRIME	Cu. Yd.	278	32	310	
11	R.S.-1 ASPHALT IN PRIME	Ton	63	7	70	
12.	ASPHALT CONCRETE PAVEMENT	Ton	3,603	362	3,965	
13.	12" CULVERT PIPE	Lin. Ft.	944	96	1,040	Future
14.	24" CULVERT PIPE	Lin. Ft.	90	10	100	
15	36" CULVERT PIPE	Lin. Ft.	198	22	220	
16.	EXTRA FOR A.C. APPROACHES	Each	41	4	45	
17.	MAIL BOX STAND (SINGLE)	Each	18	2	20	Future
18.	MAIL BOX STAND (MULTIPLE)	Each	6	1	7	
19.	ROLLER HOURS	Hour	100	10	110	
20.	72"x44" CORR. METAL PIPE	Lin. Ft.	56'	4'	60	

0623QUAN

DOUGLAS COUNTY ROAD DEPT.
ROSEBURG RESTON LOOP #5
DATE: SEPT. '69 SHEET 2 OF 6
GEORGE E. GRUBB COUNTY ENG.