

1	CLEARING & GRUBBING	LUMP	ALL	-	ALL
2	REMOVAL OF STRUCTURES & OBSTRUCTIONS	LUMP	ALL	-	ALL
3	GENERAL EXCAVATION	C.Y.	159,526	15,974	175,500
4	DITCH EXCAVATION	C.Y.	215	25	240
5	OVERHAUL	C.YD STA.	4,172	418	4,590
6	TRENCH EXCAVATION	C.Y.	1460	145	1605
7	FINISHING ROADBED & SLOPES	LUMP	ALL	-	ALL
8	OBLITERATION OF OLD ROADWAY	SQ. YD.	6700	670	7370
9	WATERING	M. GAL.	1214	121	1335
10	COARSE AGGREGATE BASE	TON	44,257	4443	48,700
11	3/4" O AGGREGATE BASE	TON	14,989	1511	16,500
12	ASPHALT CONCRETE PAVEMENT	TON	11,858	1192	13,050
13	3/4" O IN PRIME COAT	C.Y.	628	62	690
14	ASPHALT IN PRIME COAT	TON	157	18	175
15	12" CULVERT PIPE	LIN. FT.	958	97	1055
16	18" CULVERT PIPE	LIN. FT.	1530	155	1685
17	24" CULVERT PIPE	LIN. FT.	168	17	185
18	42" CULVERT PIPE	LIN. FT.	62	8	70
19	60" C.M.P. (COATED)	LIN. FT.	120	15	135
20	72" C.M.P. (COATED)	LIN. FT.	148	17	165
21	84" C.M.P. (COATED)	LIN. FT.	84	11	95
22	EXTRA FOR A.C. APPROACHES	EACH	35	5	40
23	LOOSE RIP RAP CLASS 100	C.Y.	200	20	220
24	GUIDE POSTS TYPE W-1	EACH	246	24	270
25	MAIL BOX STANDS (SINGLE)	EACH	12	3	15
26	MAIL BOX STANDS (MULTIPLE)	EACH	3	2	5
27	WEEK END WATERING	M-GAL	243	27	270
28	ROLLER HOURS	HOUR	770	80	850

FILED
RECEIVED

JUL 03 1975

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

0766QUAN

NOT REVISED
AS CONSTRUCTED

DOUGLAS COUNTY ROAD DEPT.
EDENBOWER MILLWOOD RD. NO. 6
1972 SHEET 2
GEORGE E. GRUBS COUNTY ENGR.

Rd. #6 1973 Sh. 2 of 13

(27)