

## QUANTITY SUMMARY

ITEM	UNIT	QUANTITY	ALLOWANCE	TOTAL
1 CLEARING & GRUBBING	L-SUM	ALL	—	ALL
2 GENERAL EXCAVATION (UNCLASS)	CU-YD	16,170	1615	17,785
3 DITCH EXCAVATION (UNCLASS)	CU-YD	40	5	45
4 OVERHAUL	C-YD-STA.	—	—	—
5 TRENCH EXCAVATION (UNCLASS)	CU-YD	112	13	125
6 FINISHING ROADBED & SLOPES	L-SUM	ALL	—	ALL
7 WATERING	M-GAL	168	17	185
8 COARSE AGGREGATE BASE	TON	6,316	634	6,950
9 3/4-O TOP COURSE BASE	TON	2,062	208	2,270
10 3/4-O MATERIAL IN PRIME	CU-YD	147	13	160
11 RC-250 ASPHALT IN PRIME	TON	17	2	19
12 ASPHALT CONCRETE PAVEMENT	TON	1,376	139	1,515
13 12" CULVERT PIPE	LIN FT	614	61	675
14 18" CULVERT PIPE	LIN FT	138	12	150
15 EXTRA FOR ASPHALT APPROACHES	EACH	11	1	12
16 MAIL BOX STANDS (SINGLE)	EACH	5	1	6
17 ROLLER HOURS	HOUR	97	13	110

FILED  
RECEIVED

JUL 03 1975

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE

NOT REVISED  
AS CONSTRUCTED

00000000

DOUGLAS COUNTY ROAD DEPT.  
LITTLE RIVER ROAD NO. 17  
1972 SHEET 2  
GEORGE E. GRUBB COUNTY ENGR.

Rd. #17 1972 SHEET 2

56