

## QUANTITY SUMMARY

ITEM	UNIT	QUANTITY	ALLOWANCE	TOTAL
1 CLEARING & GRUBBING	LUMP SUM	ALL	—	ALL
2 DITCH EXC.	CU. YD.	161	19	180
3 GENERAL EXC. (UNCLS.)	CU. YD.	65,931	6,619	72,550
4 OVERHAUL	C.Y.D. STA.	775.3	74.7	850
5 FINISHING ROADBED & SLOPES	LUMP SUM	ALL	—	ALL
6 TRENCH EXC. (UNCLS.)	CU. YD.	330	30	360
7 WATERING	M <sup>3</sup> GAL.	745	255	1,000
8 OBLITERATE OLD ROADWAY	STATION	7.4	.6	8
9 1/2" COARSE CRUSHED MATL. IN BASE	TON	28,500	2,850	31,350
10 3/4" COARSE CRUSHED MATL. IN BASE	TON	9,100	900	10,000
11 3/8" AGGREGATE IN PRIME COAT	CU. YD.	470	50	520
12 R.C. 250 IN PRIME COAT	CU. YD.	107	13	120
13 CLASS "B" ASPHALTIC CONC.	TON	5850	600	6,450
14 EXTRA FOR PAVING APPROACHES	EACH	19	1	20
15 12" CULVERT PIPE	LINE FT.	579	61	640
16 18" " " "	" " "	535	50	585
17 24" " " "	" " "	90	10	100
18 30" " " "	" " "	120	10	130
19 36" " " "	" " "	72	8	80
20 48" " " "	" " "	76	9	85
21 72" CORRUGATED METAL PIPE	" " "	72	8	80
22 GUARD RAIL	" "	5,375	550	5,925
23 RAIL END PIECES	EACH	22	2	24
24 GUARD RAIL BLOCKS	" "	485	45	530
25 STANDARD WOVEN WIRE FENCING	ROD	1,355	135	1,490
26 STANDARD STEEL GATES	EACH	19	1	20
27 MAIL BOX STANDS SINGLE	"	12	1	13
28 " " " MULTIPLE	"	2	1	3
29 ROLLER HOURS	HOUR	260	25	285
30 REMOVE & REINSTALL CATTLE GUARD	EACH	1	0	1

DOUGLAS COUNTY ROAD DEPT.  
 LITTLE RIVER (Buckhorn) 17  
 DATE: MAR. 70 SHEET 2  
 GEORGE E. GRUBB COUNTY ENG.

0314QUAN