

QUANTITY SUMMARY

ITEM	UNIT	QUANTITY	ALLOWANCE	TOTAL	
1	CLEARING & GRUBBING	LUMP SUM	ALL	-	ALL
2	DITCH EXCAVATION	CU YD	172	18	190
3	GENERAL EXCAVATION (UNCLASS)	CU YD	139,813	13,987	153,800
4	OVERHAUL	CYD STA	4,343	437	4,780
5	WATERING	M GAL	1,014	101	1,115
6	FINISHING ROADBED & SLOPES	LUMP SUM	ALL	-	ALL
7	TRENCH EXCAVATION (UNCLASS)	CU YD	1,406	144	1,550
8	SPECIAL BACKFILL IN DRAINS	CU YD	14	1	15
9	OBLITERATION OF OLD ROADWAY	STA	17.3	0.7	12
10	COURSE CRUSHED MATERIAL IN BASE	TONS	46,700	4,670	51,370
11	3/4"-0 MATERIAL IN BASE	TONS	14,030	1,405	15,435
12	DRY RIPRAP CLASS ONE	CU YD	114	11	125
13	CLASS B ASPHALTIC CONCRETE	TONS	9,720	980	10,700
14	RC 250 IN PRIME COAT	TONS	182	18	200
15	3/4"-0 IN PRIME COAT	CU YD	1,542	158	1,700
16	12" CULVERT PIPE	LIN FT	1,152	118	1,270
17	18" CULVERT PIPE	LIN FT	1,526	154	1,680
18	24" CULVERT PIPE	LIN FT	161	19	180
19	30" CULVERT PIPE	LIN FT	130	15	145
20	36" CULVERT PIPE	LIN FT	322	33	355
21	42" CULVERT PIPE	LIN FT	86	9	95
22	29X18" C.M.P. (COATED)	LIN FT	60	10	70
23	50X31" C.M.P. (COATED)	LIN FT	90	10	100
24	72X44" C.M.P. (COATED)	LIN FT	62	8	70
25	6" PERFORATED DRAIN PIPE	LIN FT	150	15	165
26	EXTRA FOR A.C. APPROACHES	EA	59	6	65
27	MAIL BOX STAND (SINGLE)	EA	39	6	45
28	ROLLER HOURS	HOUR	840	85	925

NOT REVISED
AS CONSTRUCTED

DOUGLAS COUNTY ROAD DEPT
LOOKINGGLASS MELROSE
DATE: 6-1970 SHEET 2
GEORGE E. GRUBB COUNTY ENG

0000SUMM