FILED
RECEIVED
JUL 15 1975
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

QUANTITY SUMMARY

	ITEM	UNIT	QUANTITY	ALLOWANCE	TOTAL
1	CLEARING & GRUBBING	L-SUM	ALL	—	ALL
2	REMOVAL OF STRUCTURES & OBSTRUCTIONS	L-SUM	ALL	—	ALL
3	DITCH EXCAVATION	CU. YD.	50	5	55
4	GENERAL EXCAVATION	CU. YD.	32,327	3223	35,550
5	OVERHAUL	C-YD. STA.	425	45	470
6	TRENCH EXCAVATION	CU. YD.	626	64	690
7	FINISHING ROADBED & SLOPES	L-SUM	ALL	—	ALL
8	WATERING	M-GAL.	707	73	780
9	WEEKEND WATERING	M-GAL.	150	15	165
10	BOTTOM COURSE BASE	TON	12,648	1272	13,920
11	TOP COURSE BASE	TON	5,992	608	6600
12	CLASS ASPHALT CONCRETE	TON	2,876	284	3,160
13	ASPHALT IN TACK COAT	TON	4	1	5
14	3/4"-0 AGGREGATE IN PRIME COAT	CU. YD.	315	35	350
15	ASPHALT IN PRIME COAT	TON	43	7	50
16	66" CMP COATED	LIN. FT.	40	5	45
17	12" CULVERT PIPE	LIN. FT.	435	40	475
18	18" CULVERT PIPE	LIN. FT.	752	73	825
19	24" CULVERT PIPE	LIN. FT.	90	10	100
20	6" PERFORATED DRAIN PIPE	LIN. FT.	615	60	675
21	SPECIAL BACKFILL IN DRAINS	CU. YD.	70	10	80
22	EXTRA FOR A.C. APPROACHES	EACH	26	4	30
23	CLASS 100 LOOSE RIP RAP	CU. YD.	297	28	325
24	MAILBOX STAND SINGLE	EACH	21	4	25
25	ROLLER HOURS	HOUR	138	12	150
26	GUARD RAIL	LIN. FT.	1525	150	1675
27	STANDARD WOVEN WIRE FENCE	LIN. FT.	4360	440	4800
28	STANDARD 14' GATES	EACH	2	1	3
29	CLASS 200 2" P.V.C. PLASTIC PIPE	LIN. FT.	1100	100	1200

0000SUMM

NOT REVISED
AS CONSTRUCTED

DOUGLAS COUNTY ROAD DEPT.
KENT CR. #100
1972 SHEET 2
GEORGE E. GRUBB COUNTY ENG.

1972
Co. Rd. #100 sht. 2 (14)