# QUANTITY SUMMARY

| | ITEM | UNIT | QUANTITY | ALLOWANCE | TOTAL |
|---|---|---|---|---|---|
| 1 | CLEARING & GRUBBING | L-SUM | ALL | — | ALL |
| 2 | GENERAL EXCAVATION | C.Y. | 3,250 | 350 | 3,600 |
| 3 | TRENCH EXCAVATION | C.Y. | 13 | 2 | 15 |
| 4 | FINISHING ROADBED & SLOPES | L-SUM | ALL | — | ALL |
| 5 | WATERING | M-GAL | 60 | 6 | 60 |
| 6 | AGGREGATE BOTTOM COARSE BASE | C.Y. | 1,280 | 120 | 1,400 |
| 7 | AGGREGATE TOP COARSE BASE | C.Y. | 610 | 60 | 670 |
| 8 | 3/4"-0 AGGREGATE IN PRIME | C.Y. | 45 | 5 | 50 |
| 9 | ASPHALT IN PRIME | TON | 11 | 1 | 12 |
| 10 | COLD MIX ASPHALT PAVING | TON | 510 | 50 | 560 |
| 11 | 12" CULVERT | LIN. FT. | 150 | 15 | 165 |
| 12 | 18" CULVERT | LIN. FT. | 70 | 5 | 75 |
| 13 | ROLLER HOURS | HOUR | 20 | 2 | 22 |

FILED
RECEIVED
JUL 03 1975
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

NOT REVISED
AS CONSTRUCTED

RD174004

DOUGLAS COUNTY ROAD DEPT.
CALLAHAN RD 174
1973 SHEET 4
GEORGE E. GRUBB COUNTY ENGR.