FILED
RECEIVED
JUL 15 1975
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

QUANTITY SUMMARY

	ITEM	UNIT	TOTAL QUANTITY	~~ALLOWANCE~~	~~TOTAL~~
1	CLEARING & GRUBBING	Lump Sum	ALL		
2	DITCH EXCAVATION	CU. YD.	5		
3	GENERAL EXCAVATION	CU. YD.	870		
4	TRENCH EXCAVATION	CU. YD.	70		
5	FINISHING ROADBED & SLOPES	Lump Sum	ALL		
6	WATERING	M-GAL.	8		
7	1½"-0 AGGREGATE BASE	CU. YD.	210		
8	3/4"-0 AGGREGATE BASE	CU. YD.	100		
9	CLASS B ASPHALT CONCRETE PVMT.	TON	105		
10	BITUMOT IN PRIME	CU. YD.	20		
11	ASPHALT IN PRIME	TON	2		
12	12" CONCRETE CULVERT PIPE	LIN. FT.	310		
13	CATCH BASIN TYPE "A"	EACH	2		
14	CLASS "B" CURB & GUTTER	LIN. FT.	450		

NOT REVISED
AS CONSTRUCTED

DOUGLAS COUNTY ROAD DEPT.
HANNA STREET #255
1972 SHEET 2
GEORGE E. GRUBB COUNTY ENGR.

00008UMM