

FILED
RECEIVED
JUL 15 1975
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

QUANTITY SUMMARY

ITEM	UNIT	QUANTITY			ALLOWANCE	TOTAL
		BURDETTE DRIVE	BEL-AIR COURT	GREEN AVE.		
1. CLEARING and GRUBBING	Lump Sum	ALL	ALL	ALL		ALL
2. GENERAL EXCAVATION	Cu. yd.	1,247	1,247	1,247		3,741
3. FINISHED ROADBED and CLOSURE	Lump Sum	ALL	ALL	ALL		ALL
4. TRENCH EXCAVATION	Cu. yd.	14	110	700		824
5. WATERING	M-Gal.	18	19	32		70
6. 12" CONCRETE CONDUIT PIPE	Lin. ft.	59	322	729		1,110
7. 12" ASBESTOS PIPE (COATED)	Lin. ft.	—	—	523		523
8. CLASS "B" CURBS	Lin. ft.	822	792	1,438		3,072
9. CATCH BASIN TYPE "A"	Each	1	4	7		12
10. MANHOLE TYPE "B" (SPALL CONCRETE)	Each	—	1	1		2
11.	5.2	4.5	7.2		17
SUBFACING						
ALTER AHEAD						
1. 6" ASPHALT BASE (6")	Cu. yd.	338	369	640		1,347
2. 3" ASPHALT BASE (3")	Cu. yd.	155	175	290		620
3. 2" ASPHALT BASE	Cu. yd.	25	29	46		100
4. ...	Ton	2.6	3.3	5.3		11.2
5. CLASS "B" OR "C" PAVEMENT (2")	Ton	150	185	292		627
THIS IS O.K.						
1. ASPHALT CONC BASE (COLD MIX) 5"	Ton	720	450	368		1,538
2. ASPHALT CONC WEARING SURFACE (COLD MIX) 3"	Ton	232	185	150		627
1. CLASS "A" UNSTABILIZED ASPHALT CONC QUANT (5")	Ton	645	460	331		1,384
2. CLASS "B" UNSTABILIZED ASPHALT CONC QUANT (2")	Ton	263	167	135		565

ASPHALT CONC BASE (COLD MIX) 5"
ASPHALT CONC WEARING SURFACE (COLD MIX) 3"

Note on plans what will be underground.

Note on plans to verify present st. sewer inlet elev. Prior to installing any storm sewer.

NOT REVISED
AS CONSTRUCTED

DOUGLAS COUNTY ROAD DEPT.
SUNNYSLOPE ROADS #278
DATE: AUG SHEET 2
GEORGE E. GRUBB COUNTY ENG.

RD278001