

FILED
RECEIVED
JUL 15 1975
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

QUANTITY SUMMARY

ITEM	UNIT	QUANTITY			TOTAL
		BURDETTE DRIVE	BEL-AIR COURT	GREEN AVE.	
1. CLEARING and GRUBBING	Lump Sum	ALL	ALL	ALL	ALL
2. GENERAL EXCAVATION	Cu. yd.	1,447	1,243	1,940	4,630
3. FINISHING ROADBED and SLOPES	Lump Sum	ALL	ALL	ALL	ALL
4. TRENCH EXCAVATION	Cu. yd.	14	110	700	824
5. WATERING	M-Gal.	18	19	33	70
6. 12" CONCRETE CULVERT PIPE	Lin. ft.	58	322	729	1,109
7. 29" X 18" A.T.C.M.P. (COATED)	Lin. ft.	—	—	523	523
8. CLASS "B" CURBS	Lin. ft.	822	792	1,458	3,072
9. CATCH BASIN TYPE "A"	Each	1	4	7	12
10. MANHOLE TYPE "B" (GRATE COVER)	Each	—	1	1	2
SURFACING					
ALTERNATE "A"					
1. 1 1/2" - 0 IN BASE (6")	Cu. yd.	338	369	640	1,347
2. 3/4" - 0 IN BASE (3")	Cu. yd.	155	175	290	620
3. 3/4" - 0 IN PRIME	Cu. yd.	25	29	46	100
4. R.S.I. IN PRIME	Ton	2.6	3.3	5.3	11.2
5. CLASS "B" or "C" A.C. PAVEMENT (2")	Ton	150	185	292	627
ALTERNATE "B"					
1. CLASS "B" A.C. PAVEMENT (5")	Ton	368	455	720	1,538
2. CLASS "B" or "C" A.C. PAVEMENT (2")	Ton	150	185	292	627
ALTERNATE "C"					
1. ASPHALT CONC. BASE (COLD MIX) (5")	Ton	331	410	648	1,384
2. ASPHALT CONC. WEARING SURFACE (COLD MIX) (2")	Ton	133	167	263	565

NOT REVISED
AS CONSTRUCTED
DOUGLAS COUNTY ROAD DEPT.
SUNNYSLOPE ROADS #278
DATE: AUG SHEET 2
GEORGE E. GRUBB COUNTY ENG.