

QUANTITY SUMMARY

	ITEM	UNIT	QUANTITY	ALLOWANCE	TOTAL
CARMEL CT.	1	FINISHING ROAD BED & SLOPES	L-SUM	ALL	
	2	TRENCH EXCAVATION	CU YD	635	
	3	WATERING	M-GAL	10	
	4	COARSE CRUSHED MATERIAL	CU YD	280	
	5	3/4" - 0 IN BASE	CU YD	130	
	6	3/4" - 0 IN PRIME	CU YD	22	
	7	R.C. 250 IN PRIME	TON	2.2	
	8	A.C. PAVEMENT	TON	130	
	9	29" X 16" C.M.P.	LIN FT	663	
	10	24" CONCRETE CULVERT	LIN FT	254	
	11	MANHOLE TYPE "B"	EACH	3	
	12	CLASS "B" CURB & GUTTER	LIN FT	593	
	13	MANHOLE TYPE "B" ALTERNATE MODIFIED	EACH	1	
	14	18" C.M. POLES	LIN FT	4	
LA CANADA DR	1	FINISHING ROAD BED & SLOPES	L-SUM	ALL	
	2	TRENCH EXCAVATION	CU YD	68	
	3	WATERING	M-GAL	11	
	4	COARSE CRUSHED MATERIAL	CU YD	340	
	5	3/4" - 0 IN BASE	CU YD	155	
	6	3/4" - 0 IN PRIME	CU YD	25	
	7	R.C. 250 IN PRIME	TON	3.3	
	8	A.C. PAVEMENT	TON	160	
	9	12" CONCRETE CULVERT	LIN FT	72	
	10	24" CONCRETE CULVERT	LIN FT	122	
	11	TYPE "A" CATCH BASIN	EACH	4	
	12	DITCH INTERCEPTOR CATCH BASIN	EACH	1	
	13	CLASS "B" CURB & GUTTER	LIN FT	749	
	14	MANHOLE TYPE "B"	EACH	1	
HEBARD ST	1	FINISHING ROAD BED & SLOPES	L-SUM	ALL	
	2	TRENCH EXCAVATION	CU YD	8	
	3	WATERING	M-GAL	4	
	4	COARSE CRUSHED MATERIAL	CU YD	102	
	5	3/4" - 0 IN BASE	CU YD	47	
	6	3/4" - 0 IN PRIME	CU YD	8	
	7	R.C. 250 IN PRIME	TON	1	
	8	A.C. PAVEMENT	TON	48	
	9	12" CONCRETE CULVERT	LIN FT	36	
	10	CLASS "B" CURB & GUTTER	LIN FT	255	
	11	TYPE "A" CATCH BASIN	EACH	2	

NOT REVISED
AS CONSTRUCTED

DOUGLAS COUNTY ROAD DEPT.
SUNNYSLOPE STS RD # 276
MAY 1975 SH. 3
GEORGE E. GRUBB COUNTY ENGR

G. Rd. # 276 SH. 3
MAY 1975
65

10278007