FILED
RECEIVED
JUL 15 1975
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

QUANTITY SUMMARY

	ITEM	UNIT	TOTAL QUANTITY	~~ALLOWANCE~~	~~TOTAL~~
	LA CANADA DRIVE				
1	TRENCH EXC	CU YD	230		
2	FINISHING ROADBED & SLOPES	L-SUM	ALL		
3	WATERING	M-GAL	30		
4	12" CONC CULV PIPE	LIN FT	380		
5	18" CONC CULV PIPE	LIN FT	130		
6	24" CONC CULV PIPE	LIN FT	120		
7	CATCH BASIN TYPE "A"	EACH	3		
8	MANHOLE TYPE "B" W/GRATE COVER	EACH	1		
9	1 1/2"-0 AGGREGATE BASE	CU-YD	800		
10	3/4"-0 AGGREGATE BASE	CU-YD	370		
11	3/4"-0 IN PRIME	CU-YD	30		
12	ASPHALT IN PRIME	TON	8		
13	CLASS "B" ASPHALT CONC. PVMT	TON	380		
14	TYPE "B" CURB & GUTTER	LIN FT	1800		
	SANTA ROSA COURT				
1	TRENCH EXC	CU-YD	130		
2	FINISHING ROADBED & SLOPE	L-SUM	ALL		
3	WATERING	M-GAL	20		
4	12" CONC CULV PIPE	LIN FT	315		
5	CATCH BASIN TYPE "A"	EACH	3		
6	1 1/2"-0 AGGREGATE BASE	CU YD	475		
7	3/4"-0 AGGREGATE BASE	CU YD	230		
8	3/4"-0 IN PRIME	CU YD	20		
9	ASPHALT IN PRIME	TON	5		
10	CLASS "B" ASPHALT CONC. PVMT	TON	235		
11	TYPE "B" CURB & GUTTER	LIN FT	900		

NOT REVISED
AS CONSTRUCTED

DOUGLAS COUNTY ROAD DEPT
SUNNYSLOPE RDS # 278
1972 SHT 2
GEORGE E GRUBB COUNTY ENGR

RD278010

1972
G. Rd. # 278 sht. 2 (68)