

1/4 S
 2
 11

Fd. brass cap mkd.
 County Surveyor's Office
 T31S R2W
 1/4 S2, S11 1966
 From which a:

34" Douglas fir original BT
 Scribes vis.
 Bears N71°W, 15.8 ft.
 10" Douglas fir BT
 Now stump
 Bears S36°E, 29.0 ft.
 9" Douglas fir BT
 Now stump
 Bears S27°W, 25.4 ft.
 10" Douglas fir BT
 Scribes vis.
 Bears S31°E, 23.0 ft.
 (Record, S34°E)

This corner lies 2.0 ft.
 North of E-W fence line,
 and 12.0 ft. East of fence
 corner. Fences bear E,
 W, and S.

NO*09 35.6"E
 2668.47 (813.350 m.)

Private

1/4 S 10 \odot 11
 S89°41'42.2"E
 1335.58 (407.085 m.)

CW 1/16

S89°41'42.2"E
 1335.58 (407.085 m.)

C1/4

S89°41'42.2"E
 2661.15 (811.119 m.)

11 \odot 12 1/4 S

Fd. brass cap mkd.
 County Surveyor's Office
 T31S R2W
 1/4 S10, S11 1966
 From which a:

22" Douglas fir BT
 With face
 Bears S35°E, 55.0 ft.
 18" cedar BT
 Scribes vis.
 Bears S33°W, 38.0 ft.
 Fence corner running N
 and E bears S45°E, 4.4 ft.

Set brass cap mkd.
 T31S, R2W, W. M.
 CW1/16, S11
 PLS 430 1979
 From which a:

10" Douglas fir, 1 scribe
 "CW1/16 S11 BT"
 Bears S54°W, 13.4 ft.
 28" Douglas fir, 1 scribe
 "CW1/16 S11 BT"
 Bears N88°E, 15.3 ft.
 Corner is 18.0 ft. South
 of an E-W fence.
 1 1/2" Iron Pipe bears
 S 89°10'E, 108.45 ft.


Set brass cap mkd.
 T31S, R2W, W. M.
 C1/4 S11
 PLS 430 1979
 From which a:

12" Douglas fir, 1 scribe
 "C1/4 S11 BT"
 Bears N82°W, 79.0 ft.
 10" Douglas fir, 1 scribe
 "C1/4 S11 BT"
 Bears N52 1/4°E, 227.5 ft.
 10" yew post at C1/4 set
 by County Surveyor Eppstein
 in 1928 ± bears S38°W,
 26.25 ft. Yew post is fence
 corner post. Fences bear E,
 W, & N.

Fd. brass cap mkd.
 County Surveyor's Office
 T31S, R2W
 1/4 S11, S12 1966
 From which a:

26" Douglas fir BT
 Mkd. by Eppstein
 Bark scribes vis.
 Bears S64°W, 54.1 ft.
 17" Douglas fir Eppstein BT
 With face
 Bears S38°E, 35.0 ft.
 Small stone with scribes
 lays beside brass cap.
 Corner is in fence corner with
 fences running N, S, and W.

U.S. Forest Service



Private

LEGEND

- Corner found \odot
- Corner set \circ
- True line marked with plastic posts and signs & trees blazed & painted red
- Line traversed

Note:
 All Bearing Trees have brass washers
 with "R.L.S. 430" nailed to lower blaze.

NO*18 56.0"E
 2663.82 (811.932 m.)

Oregon State Highway No. 227

NO*09 35.6"E
 2655.82 (809.494 m.)

W1/16 S89°57'47.9"W, 1342.82 (409.292 m.)
 (USBLM resurvey record 1971, N89°58'W, 1339.80)

11
 14
 1/4 S

Fd. brass cap mkd.
 U. S. Department of the Interior Cadastral Survey
 W1/16 S11, S14 1971
 From which a:

14" Douglas fir BT
 With face
 Bears S36°E, 33.6 ft.
 8" Douglas fir BT
 With face
 Bears N22°W, 47.8 ft.
 This corner at timber corner
 on old logging road.

Fd. brass cap mkd.
 County Surveyor's Office
 T31S R2W
 1/4 S11, S14 1966
 From which a:

18" Douglas fir stump original BT
 Piece of old scribe lying along side
 Bears S88°W, 8.6 ft. to face
 9.6 ft. to center of stump
 6" white fir BT
 Healed blaze
 Bears N9°W, 27.7 ft.
 18" white fir BT
 Scribes vis.
 Bears S61°E, 44.3 ft.

CERTIFICATE OF SURVEYOR:

I, Bruce A. Shaner, a registered land surveyor in the State of Oregon,
 hereby certify that this plat and the notes hereon or attached, are a
 correct representation of a survey I performed during November and
 December, 1979, for the U. S. Forest Service, in accordance with the
 statutes of the State of Oregon and with the articles of my contract.

B A Shaner

Bruce A. Shaner
 Registered Land Surveyor
 Oregon License 430



TILLER LAND SURVEY NO. 36 OF
 SEC. 11, T31S, R2W, W. M.,
 DOUGLAS COUNTY, OREGON
 (Contract No. 53-04HI-9-7462N)

For: Tiller Ranger District
 Umpqua National Forest

By: Shaner Engineering, Inc.
 P. O. Box 1430
 Roseburg, Oregon 97470

January 7, 1980