


MAP FILE M161-14B

FILED
Date: 8-13-2010 By: JC
This survey consists of:
Map: M161-14 A & B
Narrative:
Corner Rpt:
DOUGLAS COUNTY
SURVEYOR

**E-MILE THIN CADASTRAL
RECORD OF SURVEY FOR THE
UMPQUA NATIONAL FOREST
T.27 S, R.1 W., W.M.
SE 1/4 SEC. 7 -- S 1/2 SEC. 8
DOUGLAS COUNTY, OREGON
JUNE 21, 2010**



MAG. DECL.: 19° EAST

(A)

T27S R1W
C 3/4 S7
RLS 1654
1980

C 3/4 Sec. 7:
Found:
Brass Cap and Iron Pipe set in CSF No. M79-50,
from which:
A 9° Fir, S 42° W, 8.2 ft., healed blaze
A 10° Fir, N 82° W, 20.0 ft., healed blaze

(D)

S 1/6
S7 | S8
1971

S 1/6 between Sec. 7 & Sec. 8:
Found:
The BLM Brass Cap and Iron Pipe, from
which:
A 20° Fir, N 72 3/4° W, 10.6 ft., healed blaze
A 14° Fir, S 19 1/2° E, 22.6 ft., healed blaze

(G)

W C
S 8
E 1/6 --->
S17
1971

Witness Corner to the E 1/16
corner between Sec. 8 & Sec. 17:
Found:
The BLM Brass Cap and Iron Pipe, from
which:
A 12° Fir, N 74° E, 78.5 ft., healed blaze
A 13° Fir, S 82° W, 31.5 ft., healed blaze

(J)

T27S R1W
S8
E 1/6 -----
S17
1973
PE 2128

E 1/16 corner between Sec. 7 & Sec. 18:
Found:
The Iron Pipe and brass cap set by Barnes in 1973,
from which:
A 14° Fir, S 4 3/4° W, 60.3 ft., healed blaze
A 48° Fir, S 61° E, 63.8 ft., healed blaze

(B)

1/4
S7 | S8
1971

1/4 Sec. 7 & Sec. 8
Found:
Brass Cap and Iron Pipe set by the BLM, from
which:
A 10° Pine, N 7° W, 18.6 ft., healed blaze
A 10° Pine, S 24° E, 14.8 ft., healed blaze

(E)

T27S R1W
C
S 1/16 | S8
C
RLS 1654
1980

CS 1/16, Sec. 8:
Found:
Brass Cap and Iron Pipe set in CSF No. M79-48,
from which:
A 36° Cedar, S 20° E, 9.1 ft., healed blaze
A 6° Fir, N 50° W, 13.8 ft., healed blaze

(H)

T27S R1W
S8
1/4 -----
S17
1971

1/4 Corner between Sec. 8 & Sec. 17:
Found:
The BLM Iron Pipe and brass cap, from which:
A 14° Fir, S 21 1/4° W, 32.4 ft., healed blaze
A 54° Fir, N 9 1/2° W, 48.6 ft., healed blaze

(K)

T27S
LS 418
S7 R
1/4 ----- 1
S18 W
WC
COR 18 FT
NORTH
1963

1/4 Corner between Sec. 7 & Sec. 18:
Found:
The Brass Cap and Iron Pipe set by the County
Surveyors Office in 1963 for the Witness Corner,
from which the BT's for the Witness Corner:
A 44° Fir, S 14° W, 9.6 ft., healed blaze
A 28° Fir, N 52° E, 99.8 ft., healed blaze

(C)

T27S R1W
SE 1/6 S7
RLS 1654
1980

SE 1/16, Sec. 7:
Found:
The Brass Cap and Iron Pipe set in CSF No. M79-50
leaning considerably set by improper control. At the
correct position, reset the monument, from which:
A 18° Fir, S 44° W, 33.6 ft., healed blaze
A 16° Fir, S 83 1/2° W, 39.0 ft., healed blaze

(F)

T27S R1W
SE 1/6 S8
RLS 1654
1980

SE 1/16, Sec. 8:
Found:
The Brass Cap and Iron Pipe set in CSF No.
M79-48, from which:
A 32° Fir, N 59 3/4° E, 18.5 ft., healed blaze
A 12° Fir, N 17° W, 18.1 ft., healed blaze

(I)

T27S R1W
S7 | S8

S18 | S17
1969

Section Corner common to Secs. 7, 8, 17, & 18:
Found:
The Brass Cap and Iron Pipe set by the County Surveyors
Office in 1969, from which:
A 18° Hemlock snag, N 16° W, 20.2 ft., healed blaze
A 12° Hemlock snag, N 2° E, 21.9 ft., healed blaze
A 54° Fir, N 23° E, 31.0 ft., healed blaze
A 8° Cedar, S 50° E, 93.5 ft., healed blaze
A 12° Fir, WEST, 11.0 ft., healed blaze

REGISTERED
PROFESSIONAL
LAND SURVEYOR
[Signature]
OREGON
JULY 18, 1980
MICHAEL J. SCHWARTZ
1922

EXPIRATION DATE: JUNE 30, 2012

PLOTTER: HP DESIGNJET 500
INK: BLACK C4844a
MEDIA: CONTINENTAL MILANO JPC4M2

REVIEWED BY
John Ransom 7/13/10
SIGNATURE DATE
I CERTIFY THAT THIS SURVEY WAS PERFORMED AT
THE REQUEST OF THE
UMPQUA NATIONAL FOREST SUPERVISOR.
Clifford J. Dis 8/11/10
SIGNATURE DATE

MAP FILE M161-14B